



Club at Norwich Inn - Phase 2 - Additional Work Order #1 (As Requested)

1988 Old Pond Lane, Norwich, CT 06360

1.0 Add'l Hardscape Improvements at Clubhouse #1

Furnish and Install Add'l 1 Foot of Wall Height
Furnish and Install 4' Long Textured Concrete Step - 1 Add'l Step
Perform Circle Cut for Landscaped Bed

Notes:

1. Wall estimated as 3" Mini-Creta by Tech-Bloc
2. The estimate is based on Rocka steps by Techo-Bloc

Sub Total	\$	1,729.60
Tax	\$	109.83
Total	\$	1,839.43

Item

2.0 Install Segments of Paver Walks at Clubhouse #2 Approx 160 sq ft

Sawcut, Remove and Dispose Existing Concrete (Where Req'd)
Sawcut, Remove and Dispose Existing Asph Curb (Where Req'd)
Excavate and Compact Subgrade
Install Processed Aggregate Base and Sand Bedding
Furnish and Install New Pavers (Main and Accent)
Furnish and Install Border Edge
Install Polymeric Jointing Sand
Misc Items, Engineering Layout, and Site Clean-up

Notes:

1. Limits of walk\curb removal to be verified prior to start of work
2. Estimate based on Blu-60 pavers by Techo-Bloc
3. Estimate based on Parisien accent by Techo-Bloc
4. All excavation and compaction per industry standards
5. 5"-6" of processed aggregate base req'd
6. 1" sand layer to be placed under pavers
7. Jointing sand shall be Polymeric Sand or Equivalent
8. Existing concrete patio varies between 5" - 6" thick

Sub Total	\$	4,645.87
Tax	\$	295.01
Total	\$	4,940.88

Item

3.0 Extend Existing Trash Walks at Bldgs 8, 9, and 20 - Approx 62 Total Ft

Remove and Stockpile Existing Concrete Pavers
Minor Excavation to Remove Existing Stone Layer
Furnish Metal Edging Each Side 1\8" Thick x 4" High
Stake Edging with Steel Stakes
Install Asphalt Millings 3.0' Wide x 4" Thick
Misc Items, Fuel, and Site Clean-up

Notes:

1. Metal edging is medium duty mfd by Mid City Steel

Sub Total	\$	2,045.93
Tax	\$	129.92
Total	\$	2,175.84

Item

4.0 Furnish and Install Steps as Requested

Rocka Step at Bldg #9 - 1 Total
Rrafinatto Steps at Bldg #16 - 3 Total

Notes:

1. Remove wooden platforms

Sub Total	\$	575.00
Tax	\$	36.51
Total	\$	611.51

Prepared by Dane J. White, P.E.
Perfect Curb, LLC - Owner/Gen Mgr
CT License # - HIC.0636253
October 10, 2019

Total Cost - Phase 2 - Add'l Work Order #1 \$ 9,567.66